Assured Grounding Program Part Two

Assured Equipment Grounding Conductor Program (AEGCP)

January 1 – March 31 April 1 – June 30

July 1 – September 31 October 1 – December 31

Test

- Before first use.
- Before placing back in service after any repairs.
- After suspected damage and before returning to use.
- Every three months. Cords should be tested and taped following this color-taping schedule.

Maintain a written record of the required tests, identifying all equipment that passed the test and the last date it was tested (or the testing interval). Like the program description, make it available to OSHA inspectors and affected persons *upon demand*.

^{*} Source material taken from www.osha.gov